

AD-A095 747

AIR FORCE PACKAGING EVALUATION AGENCY WRIGHT-PATTERSON--ETC F/6 13/4
TEST AND EVALUATION OF FOAM-IN-PLACE FUEL TANK CONTAINER.(U)

DEC 80 S CHUANG

PTPD-80-22

UNCLASSIFIED

NL

1 of 1
AL
NOV 81



END
DATE
FILMED
3-81
DTIC

PROVED FOR PUBLIC RELEASE
DISTRIBUTION UNLIMITED

PTPD REPORT NO. 80-22
AFPEA PROJECT NO. 79-P7-33

12

AD A 095747

LEVEL II

SHUI-NAN CHUANG

Mechanical Engineer

Autovon 787-3362
Commercial (513) 257-3362

See 1473.

DTIC
ELECTE
S MAR 0 2 1981 D
E

TEST AND EVALUATION OF
FOAM-IN-PLACE FUEL TANK CONTAINER

HQ AFALD/PTP
AIR FORCE PACKAGING EVALUATION AGENCY
Wright-Patterson AFB OH 45433

December 1980

FILE COPY

81 3 2 025

NOTICE

When government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related government procurement operation, the United States Government thereby incurs no responsibility whatsoever; and the fact that the government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto. This report is not to be used in whole or in part for advertising or sales purposes.

ABSTRACT

One single pack, F-100 aircraft, 200-gallon fuel tank foam-in-place (FIP), reusable container fabricated by Instapak, Sealed Air Corporation, Danbury CN 06810 was tested by the Air Force Packaging Evaluation Agency (AFPEA), Wright-Patterson AFB OH 45433. The container was tested IAW Federal Test Method Standard (FTMS) 101B, MIL-STD-810C and MIL-P-116G. Although a crack, with a maximum 1/2" gap, across the bottom section of the container resulted from the temperature shock test, the container passed all of the requirements as specified for this project except the cyclic exposure test. Improvements resulting from this evaluation will be incorporated into the fabrication of two additional prototype containers for the F-4 aircraft, 370 and 600 gallon fuel tanks.

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	

PREPARED BY:

Shui-Nan Chuang
SHUI-NAN CHUANG
Mechanical Engineer

PUBLICATION DATE:

03 FEB 1981

REVIEWED BY:

Ralph Zynda
RALPH ZYDA
Chief, Design Division

APPROVED BY:

Jack E. Thompson
JACK E. THOMPSON
Director, Air Force Packaging
Evaluation Agency

TABLE OF CONTENTS

	<u>Page</u>
ABSTRACT	i
TABLE OF CONTENTS	ii
INTRODUCTION	1
CONTAINER CONFIGURATION CHARACTERISTICS	1
TEST PROCEDURES AND RESULTS	2
Rough Handling Test at Ambient Temperature	2
(a) Cornerwise Drop (Rotational) Test	2
(b) Edgewise Drop (Rotational) Test	2
(c) Pendulum-Impact Test	2
Superimposed Load Test at Ambient Temperature	3
Temperature Shock Test	3
Rough Handling Test at -40°F	3
Superimposed Load Test at -40°F	3
Rough Handling Test at 140°F	3
Superimposed Load Test at 140°F	4
Vibration Test at Ambient Temperature	4
Mechanical Handling Test at Ambient Temperature	4
Modified Cyclic Exposure Test	5
DISCUSSION	5
RECOMMENDATIONS	5
TEST PLAN	7
ILLUSTRATIONS	
Figure 1. Dimension and Load-bearing Structure of the FIP Container	9
Figure 2. General Appearance and Rough Skin of FIP Container as Received	10

Figure 3.	Gaps between Container Top and Bottom as Received	11
Figure 4.	Container Top Slipped 3" after First Pendulum-Impact Test . .	12
Figure 5.	A Layer of Foam Peeled after Second Impact Test	12
Figure 6.	Superimposed Load Test	13
Figure 7.	Top View of Crack Due to Temperature Shock	13
Figure 8.	Side View of Crack Due to Temperature Shock	14
Figure 9.	Side View of Crack Due to Temperature Shock	14
Figure 10.	Moisture Collected on Outer Surface of Polyethylene Material after Cyclic Exposure Test	15
Figure 11.	Water Collected on Outer Surface of Polyethylene Material at One Corner of the Tank	15
Figure 12.	Half-Inch Deep Pool of Water Found Inside Container Bottom after Cyclic Exposure Test	16

INTRODUCTION

Previous experiences with FIP containers for F-100, 200 gallon fuel tanks indicated that the concept was feasible for satisfying rough handling requirements, providing extended environmental protection and, consequently, extending inspection cycles and reducing life cycle costs. However, observation of the containers indicated cracking in the 2 pcf rigid foam when lifted by forklifts. Structural integrity for a new design must be such that bending and sagging will not result in cracking of the container's wall or surfaces.

The Air Force Packaging Evaluation Agency (AFPEA) initiated a development project to design and fabricate FIP containers with a load bearing structure within the foam and tie-down provision (Figure 1) for assembled aircraft fuel tanks. Under this project, three FIP, reusable containers will be fabricated by Instapak, Sealed Air Corporation, Danbury CN 06810. One single pack, F-100, 200 gallon fuel tank container was subjected to a complete mechanical and environmental test by AFPEA. The test results are presented in this report. Containers for the F-4, 370 and 600 gallon fuel tanks are chosen for service test because they are most needed in the field for storage of WRM assets.

CONTAINER CONFIGURATION CHARACTERISTICS

The single pack, F-100, 200 gallon fuel tank container (Figure 1) with

Exterior Dimension (L x W x D)	166" x 34" x 41"
Exterior Volume	134 cu. ft.
Tare Weight	328 pounds
Gross Weight	426 pounds

was made of Instapak 200, 2 pcf rigid foam and had rough skin surface and gaps between the container top and bottom (Figure 2 and 3) as received. The

joint was patched for a better seal, and the outer skin surface was painted with spar varnish aluminum paint before the test.

TEST PROCEDURES AND RESULTS

Tests were conducted in accordance with Federal Test Method Standard (FTMS) 101B, Military Standard 810C and MIL-P-116G. Table 1 is the outline of the container test plan. During the tests, a test load of 98 pounds assembled, F-100, 200 gallon fuel tank was placed in the container.

1. Rough Handling Test at Ambient Temperature

(a) Cornerwise Drop (Rotational) Test: The cornerwise drop (rotational) test was conducted in accordance with FTMS 101B, Method 5005. A 24-inch drop height was used during the test. Drops were made once to each of two diagonally opposite corners of the base.

Results: Visual inspection revealed no damage to the container.

(b) Edgewise Drop (Rotational) Test: The edgewise drop (rotational) test was conducted in accordance with FTMS 101B, Method 5008. A 24-inch drop height was used during the test. Drops were made once to each end of the container.

Results: Visual inspection revealed no damage to the container.

(c) Pendulum-Impact Test: The pendulum-impact test was conducted in accordance with FTMS 101B, Method 5012. The impact was at seven feet per second. Both ends of the container were impacted.

Results: Visual inspection revealed no damage to the fuel tank and container. However, after the first impact on one end, the container top slipped 3" (Figure 4), and an indentation was observed on the container bottom. For development purposes, edge protectors were placed between the closure straps and the container top during closure. After impact on the opposite end, the container top slipped 1 1/2" and a layer of foam, approximately 2" x 12" x 2" thick, was peeled from the bottom edge (Figure 5).

2. Superimposed Load Test at Ambient Temperature

The superimposed load test was conducted in accordance with FTMS 101B, Method 5016. A load of 3200 pounds was applied on the container and kept constant at that loading for one hour. Measurements were made at the four corners and mid-center of the sides for compression set (Figure 6).

Results: At the end of the test, a maximum of 1/8" compression was noted.

3. Temperature Shock Test

The temperature shock test was conducted in accordance with MIL-STD-810C, Method 503.1, except that temperatures were at -40°F and 140°F.

Results: After the first cycle of exposure at 140°F for 4 hours and -40°F overnight, visual inspection revealed no damage to the container. However, at the end of the second cycle of exposure at 140°F for 72 hours and -40°F for 24 hours, a wedge-shaped crack generated across a cross section of the container bottom located 36 1/2" from one end of the container (Figures 7-9). The container was not subjected to the third test cycle.

4. Rough Handling Test at -40°F

Test No. 1 was repeated except that the temperature was at -40°F.

Results: Visual inspections revealed no further damage to the container after cornerwise drops, edgewise drops and pendulum impacts. However, the container top still slipped 2 1/2" after the first impact and 1 3/4" after the second impact.

5. Superimposed Load Test at -40°F

Not performed.

6. Rough Handling Test at 140°F

Test No. 1 was repeated except that the temperature was at 140°F.

Results: The crack generated during the thermal shock test was closed after exposure at 140°F for 23 hours. Visual inspections revealed no damage to the fuel tank or container. However, the container top slipped 2 3/4" after the first impact and 2" after the second impact. At the end of the test, the crack from the temperature shock separated again.

7. Superimposed Load Test at 140°F

Test No. 2 was repeated except that the temperature was at 140°F.

Results: Measurements were made at the four corners and mid-center of the sides for the compression set. A maximum of 1/16" compression was noted at mid-center of the sides.

8. Vibration Test at Ambient Temperature

The vibration (repetitive shock) test was conducted in accordance with FTMS 101B, Method 5019. The amplitude of the vibration was 1" (double amplitude), and the frequency was 4.3 Hz during the 2-hour test.

Results: Visual inspection revealed no damage or failures in the container.

9. Mechanical Handling Test at Ambient Temperature

The mechanical handling test was conducted in accordance with FTMS 101B, Method 5011.

Lifting and Transporting by Forklift	Para 6.2
Undersling Handling	Para 6.3.1
Sling Handling with Attachments	Para 6.3.2
Pushing by Forklift	Para 6.4
Towing	Para 6.6

Results: The container was very stable while lifting or transporting by forklift, undersling handling, and sling handling with attachments. During

the pushing test, some foam was left on the concrete surface but it was not excessive. However, a piece of foam (about 3" x 15" x 3") was peeled from the end skid while towing by forklift.

10. Modified Cyclic Exposure Test

The cyclic exposure test was conducted in accordance with MIL-P-116G, para 4.4.5.2 except that the water was sprayed at 5 in/hr, including 15 minutes of 40 MPH wind at the end of each hour.

Results: At the end of the three-day test, moisture was observed on the outer surface of the polyethylene material (2 mil), which was wrapped around the fuel tank, and some droplets were noted on the tank (Figure 10). Also, approximately 1/4 cup of water was collected on the outer surface of the polyethylene material at one corner of the tank (Figure 11). After removing the fuel tank from the container bottom, tears were noted in the polyethylene material which may have been caused from shifting of the tank during testing or handling. A pool of water approximately 1/2" deep and 4 1/2' long was found inside the container bottom (Figure 12).

DISCUSSION

Although there was a crack generated during the temperature shock test, the FIP fuel tank container passed all of the requirements as specified for this project except the cyclic exposure test. However, this is the first of three FIP fuel tank containers to be fabricated in the development contract. The lessons learned from this test will be used to improve the fabrication method and procedures for the next two containers designed for the F-4, 370 and 600 gallon fuel tanks.

RECOMMENDATIONS

Following are improvements to be incorporated into the fabrication of the second and third prototype containers for the F-4, 370 and 600 gallon

fuel tanks during the development contract with Instapack, Sealed Air Corporation:

1. The bed-frame type clamps will be used in the internal load-bearing structure to allow longitudinal displacement for temperature shock adjustment.
2. A mold release will be used on walls to improve the skin surface of the container.
3. Three drainage pipes will be added in the container bottom.
4. Available space inside the container for the fuel tank will be made about 1" bigger than the fuel tank to allow for shrinkage adjustment during the chemical curing process. This will also improve the seal between the top and bottom of the container.
5. The closure joint surfaces between the container top and bottom will be at a 45° angle, instead of a 30° angle. Efforts will also be made to smooth the joint surfaces to improve the seal between the top and bottom.
6. The embedded strapping will be replaced by regular banding with load spreaders on the edges of the container. Hopefully, this will tightly secure the container top and bottom to prevent slippage during the impact test.

AIR FORCE PACKAGING EVALUATION AGENCY (Container Test Plan)					AFPEA PROJECT NUMBER 79-P7-33	
CONTAINER SIZE (L X W X D)		(GROSS) WT	(ITEM)	CUBE	QUANTITY	DATE
INT. EXT. 166"x34"x41"		426#	98#	134 ft ³	1	19 Nov 1980
ITEM NAME F-100, 200 gallon fuel tank			MANUFACTURER Instapack			
CONTAINER NAME Foam-In-Place Container				CONTAINER COST \$1,334.00		
PACK DESCRIPTION Foam-In-Place split pack configuration for assembled fuel tank.						
CONDITIONING Rough skin to be painted; gaps along the joint to be patched.						
TEST NO.	TEST METHOD	PARAMETERS		ORIENTATION	INSTRUMENTED	
1	<u>Rough Handling Test at Ambient Temperature</u>					
(a)	FTMS 101 Method 5005	24 inch drop height		Once to each of two diagonally opposite corners of base	N/A	
(b)	FTMS 101 Method 5008	24 inch drop height		Once to each end of container	N/A	
(c)	FTMS 101 Method 5012	7 FPS impact		Both ends, both sides	N/A	
2	<u>Superimposed Load Test at Ambient Temperature</u>					
	FTMS 101 Method 5016	3138 pound load		one hour, super-imposed	N/A	
3	<u>Temperature Shock</u>					
	MIL-STD-810 Method 503.1	Except that temperatures at -40°F and 140°F			N/A	
4	<u>Repeat Test No. 1 at -40°F</u>					
5	<u>Repeat Test No. 2 at -40°F</u>					
6	<u>Repeat Test No. 1 at 140°F</u>					
7	<u>Repeat Test No. 2 at 140°F</u>					
COMMENTS:						
PREPARED BY: Shui-Nan Chuang <i>Shui-Nan Chuang</i>				APPROVED BY: <i>Ralph Zynda</i>		RALPH ZYND Chief, Design Office Air Force Packaging Evaluation Agency

AIR FORCE PACKAGING EVALUATION AGENCY (Container Test Plan)					AFPEA PROJECT NUMBER	
CONTAINER SIZE (L X W X D)		(GROSS) WT	(ITEM)	CUBE	QUANTITY	DATE
INT.	EXT.					
ITEM NAME			MANUFACTURER			
CONTAINER NAME				CONTAINER COST		
PACK DESCRIPTION						
CONDITIONING						
TEST NO.	TEST METHOD	PARAMETERS	ORIENTATION	INSTRUMENTED		
8	Vibration Test at Ambient Temperature FTMS 101 Method 5019	One inch double amp. 3-5 Hz. 2 hours	As required by test	N/A		
9	Mechanical Handling Test at Ambient Temperature FTMS 101 Method 5011 Proc. 6.2, 6.3, 6.5 and 6.6	Lifting and Transporting by Forklift Undersling Handling Hoisting with sling Pushing by Forklift Towing	100 feet Suspend 2 minutes Suspend 2 minutes 35 feet in 85 seconds 100 feet in 23 seconds	N/A		
10	Modified Cyclic Exposure Test MIL-P-116 Para 4.4.5.2	Except that water spray 4+1 inch/hr and to include 15 minute 40 MPH in each hour for 4 hours		N/A		
COMMENTS: <div style="text-align: right; margin-top: 20px;"> RALPH ZYNDA Chief, Design Division Air Force Packaging Evaluation Agency </div>						
PREPARED BY: <i>Shui-Nan Chuang</i> Shui-Nan Chuang			APPROVED BY: <i>Ralph Zynda</i> Ralph Zynda			




FIGURE 1. Dimension and Load-bearing Structure of the FIP Container

FIGURE 1. Dimension and Load-bearing Structure of the FIP Container



FIGURE 2. General Appearance and Pough Skin of FIP Container as Received



FIGURE 3. Gaps between Container Top and Bottom as Received




FIGURE 4. Container Top Slipped 3" after First Pendulum-Impact Test



FIGURE 5. A Layer of Foam Peeled after Second Impact Test



FIGURE 6. Superimposed Load Test



FIGURE 7. Top View of Crack Due to Temperature Shock




FIGURE 8. Side View of Crack Due to Temperature Shock



FIGURE 9. Side View of Crack Due to Temperature Shock



FIGURE 10. Moisture Collected on Outer Surface of Polyethylene Material after Cyclic Exposure Test



FIGURE 11. Water Collected on Outer Surface of Polyethylene Material at One Corner of the Tank




FIGURE 12. Half-Inch Deep Pool of Water Found Inside

DISTRIBUTION LIST

DDC-TC (Accessions Division) Alexandria VA 22314	12
AFALD/PTP Library	20
ASD/YXA WPAFB OH 45433	5
AFALD/PT WPAFB OH 45433	1
HQ USAF/LETT Washington DC 20330	1
AFLC/LOZPP WPAFB OH 45433	1
OO-ALC/DSTC Hill AFB UT 84056	1
OC-ALC/DSP Tinker AFB OK 73145	1
SA-ALC/DSP Kelly AFB TX 78241	1
SM-ALC/DSP McClellan AFB CA 95652	1
WR-ALC/DSP Robins AFB GA 31098	1
DLSIE USA Logistics Management Center Ft Lee VA 23801	1
Tobyhanna Army Depot (SDSTO-T) Tobyhanna PA 18466	1
USA Natick Labs (DRDNA-EPS) Natick MA 01760	1
DESC (DESC-T) 1507 Wilmington Pike Dayton, OH 45444	1
NAVSUPSYSCMD (SUP-0321A) Washington DC 20376	5

DISTRIBUTION LIST (cont)

ADTC/SD3P Eglin AFB FL 32542	5
US Army Armament Research and Development Command ATTN: DRDAR-LCU-TP Dover NJ 07801	1
AFISC/SEW Norton AFB CA 92409	2

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER PTPD REPORT NO. 80-22	2. GOVT ACCESSION NO. AD-A093	3. REPORT'S CATALOG NUMBER 747
4. TITLE (and Subtitle) Test and Evaluation of Foam-In-Place Fuel Tank Container.		5. TYPE OF REPORT & PERIOD COVERED Test and Evaluation Nov - Dec 1980
7. AUTHOR(s) SHUI-NAN/CHUANG		6. PERFORMING ORG. REPORT NUMBER AFPEA Project No. 79-P7-33
9. PERFORMING ORGANIZATION NAME AND ADDRESS AFALD/PTPD WRIGHT-PATTERSON AFB OH 45433		8. CONTRACT OR GRANT NUMBER(s) 9) Rpt. for Nov-Dec 80s
11. CONTROLLING OFFICE NAME AND ADDRESS AFALD/PTPD WRIGHT-PATTERSON AFB OH 45433		10. PROGRAM ELEMENT, PROJECT, TASK AND A WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) 14 PTPD-7-11		12. REPORT DATE December 1980
		13. NUMBER OF PAGES 18
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION, DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release. Distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) <div style="display: flex; justify-content: space-between;"> <div> container aircraft shipping fuel tank </div> <div> reusable foam-in-place storage </div> </div>		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) One single pack, F-100 aircraft, 200-gallon fuel tank foam-in-place (FIP), reusable container fabricated by Instapak, Sealed Air Corporation, Danbury CN 06810 was tested by the Air Force Packaging Evaluation Agency (AFPEA), Wright-Patterson AFB OH 45433. The container was tested IAW Federal Test Method Standard (FTMS) 101B, MIL-STD-810C and MIL-P-116G. Although a crack, with a maximum 1/2" gap, across the bottom section of the container resulted from the temperature shock test, the container passed all of the		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED
SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

BLOCK 20. ABSTRACT (continued)

requirements as specified for this project except the cyclic exposure test. Improvements resulting from this evaluation will be incorporated into the fabrication of two additional prototype containers for the F-4 aircraft, 370 and 600 gallon fuel tanks.

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

DATE
FILMED
- 8